

ADDENDUM ORDER #1

DATE: March 18, 2024

NAME OF PROJECT: **Cinnamon Mountain Road & Hunter Hill Drainage & Paving Rehabilitation**

PROJECT BID DATE: April 01, 2024

OWNER: Town of Mt. Crested Butte Colorado

ENGINEER: SGM Inc.

The following clarifications and changes and/or clarifications are made to the Contract Documents:

1. **Hunter Hill Road bid item 6-H:** This bid item has been deleted in its entirety. Hunter Hill Road will only require geogrid as part of bid item 19-H Subgrade Stabilization.
2. **Hunter Hill Road bid item 19-H:** This bid item has been increased to 750 Square Yards
3. **Hunter Hill Road revised bid schedule is attached to this addendum document.**
4. This addendum form must be signed and returned with the contractors bid forms.

PREPARED BY:

/s/ G. Burgess SGM Inc.

ADDENDUM ACKNOWLEDGED BY (contractor):

(contractor signature)

Date

Project Bid Schedule (revised *per addenum 1*)
Mt Crested Butte
Hunter Hill Road

Contract Item #	Estimated Quantity	Unit	Description	Unit Price	Total Price
1-H	1	LS	Mobilization and Demobilization		
2-H	227	LF	Remove Curb and Gutter		
3-H	845	SF	Remove Valley Pan		
4-H	110	SY	Remove Concete Sidewalk and Flatwork		
5-H	4,100	SY	Full Depth Reclamation		
6-H	NA		Not Used	NA	NA
7-H	110	TON	Aggregate Base Coarse		
8-H	605	LF	Ditch Improvements		
9-H	100	LF	Culvert Cleaning		
10-H	227	LF	New Curb and Gutter		
11-H	100	SY	Concrete Flat Work		
12-H	285	LF	New Valley Pan - 36"		
13-H	1	EACH	Storm Inlet with Valley Pan Inlet/Grate		
14-H	1	EACH	Storm MH		
15-H	170	LF	18" HDPE Pipe/Culvert		
16-H	3	EACH	Flared End Sections (HDPE Culvert) 18"		
17-H	210	LF	Electrical Conduit (pipe only - no conductors) 1-1/2" Dia.		
18-H	740	TONS	Hot Mix Asphalt (prep and place)		
19-H	750	SY	Subgrade Stabilization		
20-H	1	LS	Traffic Control		
21-H	1	LS	Construction Staking/Survey		
22-H	1	LS	Minor Contract Revisions	\$25,000.00	\$25,000.00

Base Bid Total: _____

Project Total: _____